




ALTERNATE 1
ALL CONCRETE
8' WIDE SIDEWALK.
CHECK DETAIL
W/ CALTRANS AND
SWPPP, WHEN
SIDEWALKS ARE
LESS THAN 8'.



**ALL NEW CONSTRUCTION
(WITHOUT PARKWAY)**



WITH EXISTING PARKWAY ONLY



CITY OF SAN BUENAVENTURA

PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

RESIDENTIAL, COMMERCIAL, INDUSTRIAL
DRIVEWAY

STD. DET. NO.

104

APPROVED BY: *J. McDevitt*
PRINCIPAL CIVIL ENGINEER

APPROVED BY: *R. K. O.*
CITY ENGINEER R.C.E. 37064

DATE 2-25-14

SHEET
1 of 2

NOTES:

1. TOP OF "X" AS SPECIFIED BELOW:
 - A. 3' MIN. FROM PROPERTY LINE
 - B. 5' FROM ANY ABOVE GROUND UTILITY
 - C. 15' FROM ANY STREET TREE
 - D. RESIDENTIAL DRIVEWAYS - 5' MIN. FROM B.C/E.C. ALL OTHER DEVELOPMENT - 150' MIN. FROM B.C/E.C. TO TOP OF "X".
2. APPROACHES SERVING ANY ONE PROPERTY MUST BE SEPARATED AT LEAST 16 FEET BY FULL HEIGHT CURB.
3. RESIDENTIAL ACCESS - "X" EQUALS 3 FEET FOR 6 INCH AND 8 INCH CURB FACES. COMMERCIAL/INDUSTRIAL ACCESS - "X" EQUALS 6 FEET FOR 6 INCH AND 8 INCH CURB FACES.
4. "W" EQUALS 12 FEET MIN., FOR SINGLE-FAMILY RESIDENTIAL ACCESS: 16' MAX FOR ONE CAR GARAGE, 20' MAX. FOR TWO CAR GARAGE, 24' MAX. FOR THREE CAR GARAGE. "W" EQUALS 25 FEET MIN., 35 FEET MAX., FOR MULTI-FAMILY RESIDENTIAL AND COMMERCIAL ACCESS. "W" EQUALS 35'-40' FOR INDUSTRIAL ZONED PROPERTY.
5. CONCRETE SHALL BE 520-C-2500 PER SECTION 303-5 OF STANDARD SPECS. FOR PUBLIC WORKS CONSTRUCTION.
6. SEWER LATERALS SHALL NOT BE LOCATED IN DRIVEWAY.

CITY OF SAN BUENAVENTURA

PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

RESIDENTIAL, COMMERCIAL, INDUSTRIAL
DRIVEWAY

STD. DET. NO.

104

APPROVED BY: J. McDermott
PRINCIPAL CIVIL ENGINEER

APPROVED BY: [Signature]
CITY ENGINEER R.C.E. 37064

DATE 2/25/14

SHEET
2 of 2